


**Volume
4
of 5**

**FALLS CREEK DIVERSION REHABILITATION
PROJECT
GEOTECHNICAL INFORMATION
CSKT 23-018

GEOTECHNICAL REPORT**



**BY
The Confederated Salish and Kootenai Tribes
Flathead Indian Reservation – Montana**



This solicitation/specifications issued by the:

Confederated Salish and Kootenai Tribes

Natural Resources Department

P.O. Box 278

Pablo, Montana 59855

PHONE INQUIRIES

**Regarding this solicitation/specifications should be made to the office
listed below.**

See also provision B.3 of the Instructions and Conditions to Bidders.

Confederated Salish and Kootenai Tribes

**Natural Resources Department/Division of Engineering and Water
Resources**

P.O. Box 278

Pablo, MT 59855

406-676-2600

CORRESPONDENCE

**Regarding this solicitation/specifications should reference the
solicitation/specifications number.**

FALLS CREEK DIVERSION GEOTECHNICAL REPORT

for the Confederated Salish and Kootenai Tribes

May 20, 2021



FALLS CREEK DIVERSION GEOTECHNICAL REPORT FOR THE CONFEDERATED SALISH AND KOOTENAI TRIBES

Prepared for: Confederated Salish and Kootenai Tribes
P.O. Box 278
Pablo, MT 59855

Prepared by: WWC Engineering
1275 Maple Street, Suite F.
Helena, MT 59601
(406) 443-3962

Principal Authors: Scott Dunkelberger, P.E., Project Engineer
Matt Selvig, P.E., Project Engineer

Reviewed by: Drew Pearson, E.S., Project Manager
Shawn Higley, P.E., Helena Branch Manager

Date: May 2021




TABLE OF CONTENTS

INTRODUCTION	1
INVESTIGATION	1
Site Description.....	1
Geotechnical Investigation.....	1
Soil Lithology	2
Groundwater.....	2
Laboratory Testing.....	2
RECOMMENDATIONS	3
Proposed Construction.....	3
Bridge Foundation.....	3
Diversion Foundation	3
Uncontrolled Fill.....	3
Structural Fill	3
Backfill and Lateral Loads.....	4
Excavation Slopes	4
SEISMIC CONSIDERATIONS	4
SHRINK/SWELL CHARACTERISTICS	5
EARTHWORK TESTING.....	5
BASIS OF RECOMMENDATIONS	5
Review of Design.....	5
Use of Report.....	5
Level of Care	6

LIST OF TABLES

Table 1. Structural Backfill Gradation (MPWSS 3-Inch Minus Sub Base Course).....	4
Table 2. Seismic Coefficients	4
Table 3. Compaction Testing Frequency	5
Table 4. Required Relative Compaction	5

EXHIBITS

Exhibit A	Test Pit Location Map
-----------	-----------------------

LIST OF APPENDICES

Appendix A	Test Pit Logs
Appendix B	Site Investigation Photos
Appendix D	Seismic Report

INTRODUCTION

WWC Engineering (WWC) has been contracted by the Confederated Salish and Kootenai Tribes (CSKT) to complete a geotechnical investigation for the replacement of irrigation infrastructure located in the Mission Mountains on the western portion of the Flathead Reservation, Montana. The project includes the replacement of an existing timber abutment bridge (Bridge) and cast-in-place concrete canal diversion structure (Falls Creek Diversion). The proposed structures are expected to consist of cast-in-place or pre-cast concrete water diversion/conveyance structures. The purpose of this geotechnical report is to provide information on soil characteristics, groundwater conditions, and design recommendations for the bearing capacity of the soils.

INVESTIGATION

SITE DESCRIPTION

The project is located along the CSKT Tabor Feeder canal and is accessed by a single lane gravel road that generally runs parallel to the canal. The project area is in mountainous terrain where the irrigation canal flows along the hillside. The canal intercepts upstream runoff and Falls Creek can be diverted into the irrigation system at the project site. The canal and roadway were constructed by excavating the canal prism and compacting the overburden downgrade to create the lower canal bank and access road. The Falls Creek Diversion is furnished with a wasteway gate that discharges back to the natural Falls Creek channel, where a bridge along the access road crosses the channel. The Bridge also accommodates flows that overtop the Falls Creek Diversion.

The Falls Creek Diversion structure appears to be constructed as slab-on-grade reinforced concrete on native soil at or near the elevation of the adjacent canal invert (4,138 ft). The bridge abutments have vertically driven steel rails with horizontally stacked wood timbers against the native backfill soils. The bridge deck consists of welded steel rails and reinforced concrete. The channel beneath the bridge is native gravels with lateral steel supports perpendicular to the channel flow line. The channel invert elevation beneath the bridge is approximately 4,134 ft.

GEOTECHNICAL INVESTIGATION

WWC performed an on-site geotechnical investigation on May 13, 2021. During the investigation two test pits were excavated and evaluated. The location of the test pits was selected as close as possible to the bridge and Falls Creek Diversion while limiting disturbance to the existing structures, roadway, and native vegetation. The first test pit (TP-1) was conducted in the grass area adjacent to the access road, approximately 20 feet west of the bridge and 20 feet south of the canal bank. The second test pit (TP-2) was conducted on the north edge of the roadway, approximately 20 feet east of the bridge. See Exhibit A for a map of test pit locations in relation to the existing structures.

Test pit excavation extended to depths below the existing/proposed structures to identify the underlying soil characteristics. TP-1 excavated depth was 12.5 feet and TP-2 excavated depth was 10 feet. Although both test pits were planned to be excavated to a depth of 12 feet, TP-2 was terminated at a shallower depth due to space constraints and difficulty removing large boulders from the hole. Elevations of the test pits and structures are as follows:

- TP-1 Ground Elevation: 4,144.0 ft
- TP-1 Bottom Elevation: 4,131.5 ft
- TP-2 Ground Elevation: 4,141.5 ft
- TP-2 Bottom Elevation: 4,131.5 ft
- Diversion Foundation Estimated Elevation: 4,138 ft
- Bridge Channel Flow Line Elevation: 4,134 ft

Representative samples were collected at each soil layer and were field classified in general accordance with the Visual-Manual Procedure (ASTM D2488). Appendix A contains a detailed test pit log. Photos of the investigation are included in Appendix B.

SOIL LITHOLOGY

The soils encountered in both test pits were consistent and uniform. Except for the upper topsoil depth, the soil underlying the topsoil and extending to the bottom of each test pit was a single classification. The soil profiles from the test pits are summarized below:

TP-01: Approximately 0.5 foot of topsoil overlies a moist dark brown well graded and weathered gravel. The gravel contained fine to coarse grained sands and boulders that were up to 48 inches in diameter. These soils were present throughout the entire test pit depth, which terminated at 12.5 feet below the ground surface. No groundwater was present. Organics were found from a depth of 0.5 to 4 feet and appeared to be the roots from the adjacent tree and possibly timber from the original construction project.

TP-02: Approximately 0.5 foot of topsoil overlies a moist dark brown well graded and weathered gravel. The gravel contained fine to coarse grained sands and boulders that were up to 48 inches in diameter. These soils were present throughout the entire test pit depth, which terminated at 10 feet below the ground surface. No groundwater was present. Organics were found from a depth of 0.5 to 3 feet and appeared to be the roots from the adjacent tree and possibly timber from the original construction project.

GROUNDWATER

Groundwater was not encountered in the test pits during the investigation. Semi-saturated soils indicate groundwater may be at an elevation just beyond the depth of the test pit. It is reasonable to assume the soil moisture is a result of seepage from the canal or Falls Creek. The groundwater level likely fluctuates seasonally and may be a construction concern. The groundwater conditions that were encountered may only be applicable for the date of the investigation and likely vary for different times of the year.

LABORATORY TESTING

Given the nature of the project, anticipated shallow foundations, and the apparent soil conditions, further laboratory testing and laboratory classification in addition to visual classifications was not conducted.

RECOMMENDATIONS

PROPOSED CONSTRUCTION

The proposed bridge replacement is expected to be a precast concrete box culvert, precast bridge with shallow footing abutments, or an open bottom culvert with strip footing abutments. Each of these alternatives will have a similar span and depth as the existing bridge, but the size may be slightly modified based on the hydraulic analysis. The diversion is expected to be replaced with either precast or cast-in-place concrete with a geometry similar to the existing structure. Both structures will be located in the same place as the existing structure and are expected to be founded on structural fill placed on compacted, in-situ soil.

Bridge Foundation

Bridge Abutments: WWC suggests constructing the proposed bridge abutments with reinforced concrete spread footings founding on compacted structural fill. The bottom of footing elevation should be set below the scour zone of the channel. Footings should be constructed on an 18-inch-deep layer of compacted structural backfill meeting the specifications as described in the Structural Fill section of this report.

Culverts: WWC suggests founding precast box culverts on 18 inches of compacted structural backfill meeting the specifications, as described in the Structural Fill section of this report. Cut-off walls should be used and set to a depth below the scour depth of the channel.

Diversion Foundation

WWC suggests the structure be either precast or cast-in-place slab-on-grade. The structure should be placed on 18 inches of compacted structural backfill meeting the specifications, as described in the Structural Fill section of this report.

Uncontrolled Fill

Existing native soils are suitable as fill material and may be used as backfill with the following limitations. Rocks and boulders with a diameter greater than 6-inches shall not be located within two feet of precast or cast-in-place concrete. All organics should be removed from backfill material and exposed subgrades. In the event debris, deleterious materials, unsuitable, or loose backfill material is encountered, the material must be removed and replaced with suitable compacted backfill. Should construction occur in colder temperatures, appropriate winter construction techniques must be used. Fill must not be placed on top of frozen soils, and all deleterious materials must be completely removed. Fill may contain large rocks if large rocks are not placed next to each other and voids are filled in with fine soils.

STRUCTURAL FILL

The proposed foundations should be founded on a structural fill layer consisting of two 9-inch lifts (18-inches total) of structural backfill meeting the gradation provided in Table 1. The structural fill's footprint should extend horizontally past all foundation dimensions by 12 inches in each direction.

Table 1. Structural Backfill Gradation (MPWSS 3-Inch Minus Sub Base Course)

SIEVE SIZE	PERCENT PASSING
3-inch	100
No. 4	25 - 60
No. 40	10 - 30
No. 200	2 - 10

Structural fill and subgrade should be compacted to a standard relative compaction (ASTM D698) of at least 98 percent. Provided the compaction of the subgrade soils are met, an allowable bearing capacity of 2,000 pounds per square foot (psf) can be used for bridge and diversion design. A modulus of subgrade reaction, k_s of 100 pounds per square inch per inch (psi/in) of deflection can be used for reinforcement design.

Backfill and Lateral Loads

Backfill against the exterior concrete walls may consist of native gravels (<6" dia.) or the structural backfill listed in Table 1. Backfill should be placed in 9-inch (maximum) loose lifts, and each lift should be compacted to a standard relative compaction of at least 95 percent. Care should be taken not to over-compact the backfill or use large equipment within 5 feet of the wall to minimize excessive lateral wall loading.

Excavation Slopes

For excavations, the site soils meet the Occupational Safety & Health Administration's (OSHA) 29 CFR Part 1926 requirements for a Type C soil. The steepest unsupported slope within a Type C soil is limited to 1.5H:1V.

SEISMIC CONSIDERATIONS

The Project area is located on the boundary of the Northern Intermountain Seismic Belt, which is a relatively active seismic zone. According to ASCE 7-16 and Risk Category I, Seismic coefficients are presented in Table 2. The seismic coefficients data sheet is included in Appendix C.

Table 2. Seismic Coefficients

PARAMETER	COEFFICIENT
Risk Category	I
Seismic Design Category	D
Mapped Spectral Response Acceleration Parameter, S_s for 0.2 second	0.701
Mapped Spectral Response Acceleration Parameter, S_1 for 1.0 second	0.230
Adjusted Maximum Considered Earthquake Spectral Response Acceleration Parameter, S_{MS}	0.869
Adjusted Maximum Considered Earthquake Spectral Response Acceleration Parameter, S_{M1}	See ASCE 7-16, Section 11.4.8
Design Spectral Response Acceleration Parameter, S_{DS}	0.579
Design Spectral Response Acceleration Parameter, S_{D1}	See ASCE 7-16, Section 11.4.8

SHRINK/SWELL CHARACTERISTICS

The volume change potential of the native subgrade soils is considered low based on the non-plastic soils. No additional measures to reduce shrink/swell are necessary.

EARTHWORK TESTING

WWC recommends that a qualified inspector perform compaction testing for subgrade, structural fill, base course, and backfill. Table 3 lists the suggested minimum compaction testing frequency.

Table 3. Compaction Testing Frequency

LOCATION	FREQUENCY
Beneath Bridge Footings	1 test per 25 linear feet of footing per lift
Beneath Diversion Slab/Box Culvert	1 test per 400 square feet per lift
Concrete Wall Backfill	1 test per 50 linear feet per lift

Table 4 summarizes the material compaction specifications. Compaction testing should be performed on subgrade, structural fill, base course, and backfill.

Table 4. Required Relative Compaction

LOCATION REQUIRED	RELATIVE COMPACTION STANDARD
Beneath Bridge Footings	98% ASTM D698
Beneath Diversion Slab/Box Culvert	98% ASTM D698
Concrete Wall Backfill	95% ASTM D698

Concrete testing frequency should be performed in accordance with project specifications and/or inspecting engineers' requirements.

BASIS OF RECOMMENDATIONS

The analyses and recommendations submitted in this report are based upon the test pits dug during the subsurface investigation. Often, variations occur within the subgrade, the nature and extent of which do not become evident until additional exploration or construction is conducted. WWC recommends that, during earthmoving operations, a qualified geotechnical engineer be present to evaluate the foundation soils to verify their resemblance to those encountered during the site investigation. WWC should be alerted if during excavation soil conditions appear inconsistent with this soil investigation.

REVIEW OF DESIGN

This report is based on WWC's understanding of the proposed project. If the location or design changes, please consult WWC to verify that these recommendations are still applicable.

USE OF REPORT

This report is for the exclusive use of CSKT and their design team. In the absence of WWC's written approval, WWC makes no representation and assumes no responsibility to other parties regarding this report. The data, analyses, and recommendations may not be appropriate for other structures or purposes. Other parties contemplating other structures or purposes should contact WWC.

LEVEL OF CARE

Services performed by WWC Engineering personnel for this project have been conducted with the level of care and skill ordinarily exercised by members of the profession currently practicing in this area under similar budget and time restraints. No warranty, expressed or implied, is made.

EXHIBITS



FALLS CREEK DIVERSION REHABILITATION

TEST PIT LOCATIONS

LAKE COUNTY, MT

PREPARED FOR

**CONFEDERATED SALISH AND
KOOTENAI TRIBES**

P.O. BOX 278
PABLO, MT 59855

DESIGNED BY: DP
DRAWN BY: MJS
CHECKED BY: DP
DATE: 5/20/21

PREPARED BY

 **WWC** ENGINEERING

1275 MAPLE STREET, SUITE F
HELENA, MT 59601
(406) 443-3962
www.wwcengineering.com

EXHIBIT

A

APPENDIX A

TEST PITS

WWC Engineering

GEOTECHNICAL ENGINEERING AND SOILS

[illegible]

ABBREVIATIONS

SWL – Static Water Level
ST – Shelby Tube Sample
GS – Geochemical Sample
O - Petroleum Odor

DBS – Disturbed Bulk Sample
REF – Refusal
SPT – Standard Penetration Test with
 Split Barrel Sample (ASTM D-1586)

CAL – California Tube Sample
ZP – Ziplock Bag Sample
LA – Laboratory Analysis
PID – Instrument Response

WWC Engineering

GEOTECHNICAL ENGINEERING AND SOILS

[illegible]

ABBREVIATIONS

SWL – Static Water Level
ST – Shelby Tube Sample
GS – Geochemical Sample
O - Petroleum Odor

DBS – Disturbed Bulk Sample
REF – Refusal
SPT – Standard Penetration Test with
 Split Barrel Sample (ASTM D-1586)

CAL – California Tube Sample
ZP – Ziplock Bag Sample
LA – Laboratory Analysis
PID – Instrument Response

APPENDIX B

PHOTOS



IMG_5356.JPG



IMG_5357.JPG



IMG_5358.JPG



IMG_5359.JPG



IMG_5360.JPG



IMG_5361.JPG



IMG_5362.JPG



IMG_5364.JPG



IMG_5365.JPG



IMG_5366.JPG



IMG_5367.JPG



IMG_5368.JPG



IMG_5369.JPG



IMG_5370.JPG



IMG_5371.JPG



IMG_5372.JPG



IMG_5373.JPG



IMG_5374.JPG



IMG_5375.JPG



IMG_5376.JPG



IMG_5377.JPG



IMG_5378.JPG



IMG_5379.JPG



IMG_5380.JPG



IMG_5381.JPG



IMG_5382.JPG



IMG_5383.JPG



IMG_5384.JPG



IMG_5385.JPG



IMG_5386.JPG



IMG_5387.JPG



IMG_5388.JPG



IMG_5389.JPG



IMG_5390.JPG



IMG_5391.JPG



IMG_5392.JPG



IMG_5393.JPG



IMG_5394.JPG



IMG_5395.JPG



IMG_5396.JPG



IMG_5397.JPG



IMG_5398.JPG



IMG_5399.JPG

APPENDIX C

SEISMIC DATA



Hazards by Location

Search Information

Coordinates: 47.3199306, -114.0939979

Elevation: 2943 ft

Timestamp: 2021-05-18T22:40:10.909Z

Hazard Type: Seismic

Reference Document: ASCE7-16

Risk Category: I

Site Class: D-default



Basic Parameters

Name	Value	Description
S_S	0.701	MCE_R ground motion (period=0.2s)
S_1	0.23	MCE_R ground motion (period=1.0s)
S_{MS}	0.869	Site-modified spectral acceleration value
S_{M1}	* null	Site-modified spectral acceleration value
S_{DS}	0.579	Numeric seismic design value at 0.2s SA
S_{D1}	* null	Numeric seismic design value at 1.0s SA

* See Section 11.4.8

▼Additional Information

Name	Value	Description
SDC	* null	Seismic design category
F_a	1.239	Site amplification factor at 0.2s
F_v	* null	Site amplification factor at 1.0s
CR_S	0.911	Coefficient of risk (0.2s)
CR_1	0.927	Coefficient of risk (1.0s)
PGA	0.304	MCE_G peak ground acceleration
F_{PGA}	1.296	Site amplification factor at PGA
PGA_M	0.394	Site modified peak ground acceleration

T_L	6	Long-period transition period (s)
SsRT	0.701	Probabilistic risk-targeted ground motion (0.2s)
SsUH	0.77	Factored uniform-hazard spectral acceleration (2% probability of exceedance in 50 years)
SsD	3.173	Factored deterministic acceleration value (0.2s)
S1RT	0.23	Probabilistic risk-targeted ground motion (1.0s)
S1UH	0.248	Factored uniform-hazard spectral acceleration (2% probability of exceedance in 50 years)
S1D	1.273	Factored deterministic acceleration value (1.0s)
PGAd	1.269	Factored deterministic acceleration value (PGA)

* See Section 11.4.8

The results indicated here DO NOT reflect any state or local amendments to the values or any delineation lines made during the building code adoption process. Users should confirm any output obtained from this tool with the local Authority Having Jurisdiction before proceeding with design.

Disclaimer

Hazard loads are provided by the U.S. Geological Survey [Seismic Design Web Services](#).

While the information presented on this website is believed to be correct, ATC and its sponsors and contributors assume no responsibility or liability for its accuracy. The material presented in the report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the report provided by this website. Users of the information from this website assume all liability arising from such use. Use of the output of this website does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site described by latitude/longitude location in the report.